

Hubbardston Fiscal Year 2024 - 2028 Road Plan							
Road	FY24	FY25	FY26	FY27	FY28	Beyond	Notes
Pitcherville Road	\$271,000.00						The proposed improvements include a 3,125-foot application of 20% crumb rubber from pole#5 to pole#27, as well as 4,425 feet of reclaim with emulsion and 3 inches of hot mix asphalt paving from Gardner Rd. to pole#5 and from pole#27 to Templeton town line with a berm.
Birches Road	\$112,000.00						The plan involves reclaiming with emulsion and paving with 3 inches of hot mix asphalt, including a berm, from Pitcherville Rd. to Ragged Hill Rd.
Cross Road	\$131,000.00						The proposal includes reclaiming 2,370 feet with emulsion and paving it with 3 inches of hot mix asphalt, along with a berm, between Ragged Hill Rd. and New Templeton Rd.
New Westminster Road		\$450,000.00					The project involves milling and paving 2 inches of hot mix asphalt from the railroad tracks to Mare Meadow Ln, with an additional \$100,000 needed to complete the project.
Elm Street			\$100,000.00				Reclaim with emulsion and pave with 3 inches of hot mix
Brigham Street			\$183,000.00				The proposal involves reclaiming with emulsion and paving 3 inches of asphalt, along with berm and basin work from Main St. to the bridge.
Barre Road			\$172,000.00				Mill and pave 2 inches of hot mix asphalt from Elm St. to Twin Hill Rd.
Barre Road Cut-Off			\$15,000.00				Reclaim and pave the entire road with 3 inches of hot mix asphalt.
Parsons Road			\$27,000.00				The proposal includes reclaiming with emulsion and paving 3 inches of hot mix asphalt
Dogwood Road N				\$100,000.00			The plan is to reclaim with emulsion and pave with 3 inches of hot mix asphalt on the entire road.
Laurel Street				\$80,000.00			The proposal involves reclaiming with emulsion and paving with 3 inches of hot mix asphalt on the entire road.
Geordie Lane				\$200,000.00			The project aims to reclaim and pave with 3 inches of hot mix asphalt on the entire road.
Dogwood Road S				\$100,000.00			The plan includes reclaiming and paving with 3 inches of hot mix asphalt on the entire road.

New Templeton Road					\$451,000.00		The proposed plan involves milling and filling 2 inches of asphalt from Rt.68 to Pole #23, followed by reclaiming with emulsion and paving with 3 inches of hot mix asphalt with a berm from Pole #23 to Cross Rd.
Bickford Pond Rd						\$140,000.00	This project includes Full Depth Reclamation (FDR) with 3 inches of hot mix asphalt, along with basin work, for Tahanto Rd., Brookside Dr., and Forest Dr.
Ed Clark Rd.						\$125,000.00	This project involves Full Depth Reclamation (FDR) with emulsion and 3 inches of hot mix asphalt, along with basin work.
High St.						\$265,000.00	This project entails Full Depth Reclamation (FDR) with emulsion and 3 inches of hot mix asphalt, along with basin work.
Old Princeton Rd.						\$565,000.00	This project includes Full Depth Reclamation (FDR) with emulsion and 3 inches of hot mix asphalt, along with basin work and a berm from Rt.68 to Healdville Rd. intersection.
Old Princeton Rd. Cut-off						\$105,000.00	This project involves Full Depth Reclamation (FDR) with emulsion and 3 inches of hot mix asphalt, along with a berm.
Natty Pond Dr.						\$212,000.00	This project entails Full Depth Reclamation (FDR) with emulsion and 3 inches of hot mix asphalt, along with a berm.
New Templeton Rd.						\$280,000.00	This project involves milling and filling 2 inches of hot mix asphalt, along with a berm.
Simonds Hill Rd.						\$285,000.00	This project includes Full Depth Reclamation (FDR) with emulsion and 3 inches of hot mix asphalt, along with basin work.
Brigham St.						\$565,000.00	This project involves milling and filling 2 inches of hot mix asphalt with a berm from Bridge to New Westminster Rd.
TOTAL	\$514,000.00	\$450,000.00	\$497,000.00	\$480,000.00	\$451,000.00	\$2,542,000.00	